



Scale: 1:200 @ A1

All changes to this CAD generated drawing MUST be made via the master CAD file. This is an unpublished work the copyright in which vests in Telent Technology Services limited. All rights reserved. The information contained herein is confidential and the property of Telent Technology Services limited and is supplied without liability for errors or omissions. No part may be reproduced, disclosed or used except as authorised by contract or other written permission. The copyright and the foregoing restriction on reproduction and use extend to all media in which the information may be embodied.

	<p>The following information has been collected from pre-construction information and the telent CDM hazard management process.</p>	
Hazards		
1.	Underground HV Cables within the vicinity of works.	
2.	Underground LV Cables within the vicinity of works.	
3.	Gas Mains within the vicinity of works.	
4.	Underground BT Cables within the vicinity of works.	
5.	Underground Virgin Media Cables within the vicinity of works.	
6.	Underground Water Mains within the vicinity of works.	
7.	Street Lighting cables within the vicinity of works.	
<p>Statutory undertakers information has been provided by customer. All other information has been obtained from site survey and online search.</p>		

- CIVILS KEY:**
- New 400mm x 400mm Tactile Paving (Red in colour).
 - New Kerbing.
 - Footway / Central Refuge Island to be resurfaced to a depth of 25mm.
 - Controller & Termination Cabinet Root / Feeder Pillar Base Area.
- Notes:**
1. New tactile paving will be laid on 25mm motor and 100mm type 1 sub base, formation to be treated with weed killer.
 2. Footway / central refuge island construction to be 100mm type 1 sub base to clause B03 with 6mm surface course to clause 11055, formation to be treated with weed killer. PCC footpath CL50A150EF edging with bed and backing. Estimated Total Area: 510m²
 3. Any areas of carriageway reinstatement are to be of a suitable material and construction, to match the existing carriageway.
 4. All new kerbstones are to match and tie in with existing kerb stones.
 5. New Pedestrian Studs to be metallic non-slip type.
 6. Drawing to be read in conjunction with the works specification and with the following drawings:
- 359781-TS01
 359781-TS02
 359781-CV01
 359781-CV03
 359781-SC
 359781-RM

ISSUED FOR CONSTRUCTION.

Iss Rev	Date	Description	By	Chkd	App
03	00	06/12/2023			
02	00	13/11/2023			
01	00	07/11/2023			

Title:
CV02 - Wood Green Road / Myvod Road
Sandwell
Civils Drawing



Project No: S01241
Scale: As shown
Date: 28/06/2023

Drawn: RDG
CAD File Name: 359781-TS-iss03-Rev00 (Construction)

telent
Design Telephone: +44 (0)1926 693024
Design Email: design.services@telent.com
For Tendering information/services:
Tendering Telephone: +44 (0)1926 693910
Tendering Email: estimating@telent.com

Technology Services Ltd.
Point 3, Haywood Road, Warwick, CV34 5AH, United Kingdom

Originator: RDG	Checked: DJWR	Approved: PJS	Approval Date: 07/11/2023
DRAWING No: 359781-CV02	ISS: 03	REV: 00	

Original Size: A1